

TABELA ROBÓT ZIEMNYCH						Załącznik Nr	
ULICA ZIELONA W SKÓRCZU						1	
Kilometr	Wykop	Nasyp	Pow. Śr. Wykop	Pow. Śr. Nasyp	Odległość	Objetość	Objetość
przekroju						Wykop	Nas. Niekon.
[km]	[m ²]	[m ²]	[m ²]	[m ²]	[m]	[m ³]	[m ³]
0+000,00	4,600	0,100					
			4,60	0,10	30,00	138,00	3,00
0+030,00	4,600	0,100					
			2,70	0,60	30,00	81,00	18,00
0+060,00	0,800	1,100					
			0,75	1,25	30,00	22,50	37,50
0+090,00	0,700	1,400					
			0,80	1,35	30,00	24,00	40,50
0+120,00	0,900	1,300					
			1,00	1,10	30,00	30,00	33,00
0+150,00	1,100	0,900					
			1,40	0,70	30,00	42,00	21,00
0+180,00	1,700	0,500					
			1,10	1,70	30,00	33,00	51,00
0+210,00	0,500	2,900					
			0,60	2,85	30,00	18,00	85,50
0+240,00	0,700	2,800					
			1,80	1,75	30,00	54,00	52,50
0+270,00	2,900	0,700					
			2,15	1,00	30,00	64,50	30,00
0+300,00	1,400	1,300					
			1,45	1,05	30,00	43,50	31,50
0+330,00	1,500	0,800					
			1,15	1,65	30,00	34,50	49,50
0+360,00	0,800	2,500					
			1,00	2,80	30,00	30,00	84,00
0+390,00	1,200	3,100					
			1,35	2,00	30,00	40,50	60,00
0+420,00	1,500	0,900					
			0,85	2,30	30,00	25,50	69,00
0+450,00	0,200	3,700					
			0,55	3,35	30,00	16,50	100,50
0+480,00	0,900	3,000					
			1,20	2,85	30,00	36,00	85,50
0+510,00	1,500	2,700					
			1,15	2,95	30,00	34,50	88,50
0+540,00	0,800	3,200					
			0,95	3,85	30,00	28,50	115,50
0+570,00	1,100	4,500					
			0,55	2,25	30,00	16,50	67,50

TABELA ROBÓT ZIEMNYCH						Załącznik Nr	
Kilometr	Wykop	Nasyp niekonstrukcyjny	Pow. Śr. Wykop	Pow. Śr. Nasyp niekon.	Odległość	Objętość	Objętość
przekroju						Wykop	Nas. Niekon.
[km]	[m ²]	[m ²]	[m ²]	[m ²]	[m]	[m ³]	[m ³]
0+600,00	2,600	3,100					
			2,05	2,65	30,00	61,50	79,50
0+630,00	1,500	2,200					
			1,45	2,50	30,00	43,50	75,00
0+660,00	1,400	2,800					
			1,15	3,15	30,00	34,50	94,50
0+690,00	0,900	3,500					
			5,85	1,85	30,00	175,50	55,50
0+720,00	10,800	0,200					
			5,80	1,30	30,00	174,00	39,00
0+750,00	0,800	2,400					
			0,55	3,20	30,00	16,50	96,00
0+780,00	0,300	4,000					
			0,65	3,35	30,00	19,50	100,50
0+810,00	1,000	2,700					
			0,55	4,40	30,00	16,50	132,00
0+840,00	0,100	6,100					
			0,10	5,00	30,00	3,00	150,00
0+870,00	0,100	3,900					
			0,60	3,20	30,00	18,00	96,00
0+900,00	1,100	2,500					
			1,15	2,75	30,00	34,50	82,50
0+930,00	1,200	3,000					
			0,85	2,85	30,00	25,50	85,50
0+960,00	0,500	2,700					
			0,55	2,85	30,00	16,50	85,50
0+990,00	0,600	3,000					
			0,50	2,30	30,00	15,00	69,00
1+020,00	0,400	1,600					
			0,90	1,65	30,00	27,00	49,50
1+050,00	1,400	1,700					
			1,25	2,15	30,00	37,50	64,50
1+080,00	1,100	2,600					
			2,45	1,40	30,00	73,50	42,00
1+110,00	3,800	0,200					
			3,80	0,20	2,50	9,50	0,50
1+112,50	3,800	0,200					
						Wykop [m3]	Nasyp [m3]
OGÓŁEM ROBÓT ZIEMNYCH						1615	2521